

Town of Bethel
Standard Erosion and Sedimentation Control Notes

1. All erosion and sedimentation controls shall be constructed, installed and maintained in accordance with the 2002 Connecticut Guidelines for Soil Erosion and Sediment Control and Town of Bethel regulations.
2. All control measures shall be installed as shown on the plan(s).
3. All control measures shall be inspected and approved by the Town prior to commencement of any work, including pre-construction clearing and grubbing.
4. All control measures shall be maintained and upgraded as required to achieve proper sediment control throughout the construction period and until all disturbed areas have been thoroughly stabilized.
5. No control measures shall be removed without approval from the Town.
6. Additional control measures shall be installed during the construction period if deemed necessary by the Town or its authorized agent.
7. The limits of clearing, grading and disturbance, as shown on the plan(s), shall be kept to a minimum within the approved area of construction. All areas outside the limits of clearing shall remain totally undisturbed.
8. Any control measures retaining sediment over ½ their height shall have the sediment immediately removed, and all damaged control measures shall be removed and replaced.
9. All catch basins located down-grade of the site shall be protected by placing filter fabric beneath the grate until all disturbed areas have been thoroughly stabilized.
10. All new and existing catch basins located on the site shall be protected by staked haybales and by placing filter fabric beneath the grate until all disturbed areas have been thoroughly stabilized.
11. All sediment shall be immediately removed from new and existing drainage structures and piping impacted by the proposed construction.
12. Sediment removed from control measures and drainage facilities shall be disposed of in a manner that is consistent with state and local regulations.
13. The planting seasons for the specified seed mixture shall be as defined in the 2002 Connecticut Guidelines for Soil Erosion and Sediment Control, unless directed otherwise by the Town. Outside of these specified dates, areas will be stabilized with haybale check dams, filter fabric, or woodchip mulch as required to control erosion.
14. The Contractor shall take all necessary measures to ensure that no drainage from Town roads enters the site during or after construction.
15. The Contractor shall be responsible to control dust and wind erosion throughout the life of the contract. The Contractor shall control dust to prevent a hazard to traffic on adjacent roadways.
16. Temporary stockpiling of construction materials shall only be allowed in the locations shown on the plan(s). Stockpile areas shall be fully enclosed by silt fence.
17. All groundwater extracted during dewatering of excavations shall be directed to a temporary sedimentation basin.
18. The Contractor shall be responsible for implementing the Erosion and Sedimentation Control Plan. This includes the installation and maintenance of all control measures, informing all parties engaged on the construction site of the requirements and objectives of the plan, and notifying the Town of any transfer of this responsibility.